

Adtran Network Switch Replacement

TLM-07- Replace TPX Adtran EOL Switches with new models from TPX

AGENDA

- 1. Project Scope
- 2. Overview & Requirement
- 3. Device Setup & Information
- 4. Timeline



Project Scope

Overview

Problem Statement

Adtran switches are part security standards, the Adtran switches nearing or at End of Life (EOL) are being replaced of TPX managed and operated infrastructure. To ensure compliance with

Recommended Solution

TPx has decided to replace all Adtran switches with Juniper switches due to Adtran's End-of-Life status. They will replace switches one at a time, minimizing downtime to less than 5 minutes per switch. In case of simultaneous replacement, downtime may extend to 30 minutes.



Project Tracking

- SCR CA-274977
- Contract CN31

Project Scope

Accenture Scope of Work

- The defined scope of work is limited to addressing specific identified gaps or required feature enhancements.
- In the absence of well defined requirements or a requirement traceability matrix our scope remains vulnerable to expansion, especially with the emergence of new standards, updates, or requests from consortium or internal teams, potentially leading to scope creep during this project.
- Any additional effort or costs resulting from this potential scope creep are not included in the current effort and would necessitate a separate contract change for undertaking.
- TPX equipment is rental and CalSAWS will not bear the cost of the hardware.
- TPX provides Adtran as part of WAN as a service, this hardware replacement effort will be borne by TPX.
- -Effort documented in this project TLM-07 covers Project Planning and Coordination, Communication with Counties and Testing with TPX
- TPX to provide mounting kits for the new hardware and will ensure redundancy.
- -TPX will ensure new hardware compliance with TPX hardening policies. CalSAWS policies (NIST & CIS) will be conveyed as requirements
- Changes will have to be performed across all 150+ sites (Data Center, Project, Managed County Sites, POP County Sites)
- Dependency on hardware procurement, supply chain management and direction under TPX management will determine timeline

Limitations and Out of Scope

- Replacing cables
- Replacing the VM Ware Velocloud devices which are NOT End of Life

Sequence of Activity


Phase	Description	Downtime	Impact	Duration of Visit / Activity at Site
Assessment	This assessment is to <u>evaluate power and space</u> availability at the sites MDF/MPOE room. Project would dispatch Site Technicians for Site Assessment on [Date & Time].	None	None, this is a visual inspection.	1-2 hours during standard business hours.
Remediation	In case there are any actionable outcomes from the above assessment Project would notify you separately with specific details.	May vary based on level and type of remediation work		
Staging	This is a cutover activity in accordance with the Cutover Approach. This staging would involve: Mounting & Powering on New Juniper Switch Cabling and Interconnectivity between devices Configuration Testing (ping) Project dispatches site technician from Gainwell to site	45 Min to 1 Hour	High , the new setup would be installed removing the OLD switch. Users should see disruption for 30 mins	Installation will be done after business hours
Juniper Switch Implementation	TPx configures the SD WAN hardware to establish connection between CalSAWS router and TPx Velocloud. TPx configures and validates reachability to Juniper switch TPx validates site is up from their monitoring. CalSAWS validates CalSAWS routers are up and can be remotely administered. Project dispatches site technician from Gainwell to site.	45 Min to 1 Hour	High , the new setup would be installed removing the OLD switch. Users should see disruption for max 45 min	Duration is 1-2 hours
Juniper Switch Integration	County network connectivity to CalSAWS is established. Cabling between CalSAWS and County edge Interconnectivity between County and CalSAWS router/firewall Network configuration Testing (ping) Project dispatches site technician from Gainwell to site	None	Low, The CalSAWS connection will be established in parallel with CalWIN sites. The connection and network configuration on County network will be independent of CalWIN.	Duration 1 hour

Requirements

Adtran Network Switch Replacement	
PREREQUISITES	<p>Site surveys of the sites not completed yet.</p> <p>Shipment of the new Juniper switches to our warehouse</p> <p>CIT distribution to all the Counties</p>
ACTION ITEMS – County IT	<p>Respond to email communication sent to County on approval to schedule a maintenance window for the site</p> <p>Allow access to the server room for TPx and CalSAWS remote technician</p>
ACTION ITEMS – CalSAWS IT	<p>Send County an email communication to get approval</p> <p>Create and schedule the change request for the approved site</p> <p>Coordinate with the site Engineer & TPx during the scheduled maintenance window</p> <p>Update network documentation and diagrams</p>
TESTING	<ul style="list-style-type: none">• Check Orchestrator & SolarWinds for the status of the site.• Login to the core switch to check BGP status by:<ul style="list-style-type: none">- ” Sh Ip bgp all summary” and ”Sh Ip BGP neighbor”• Ping the AWS IP 67.21.40.200


High Level Design

Current Design





Port 4 to GE6: Management port connection
Port 2 to GE6 - Circuit connection
Port 10 to Port 10 - Trunk port connection
GE6 to GE6 - SD-WAN (Velo cloud) connection

New Design



Port 4 to GE4 - Management port connection
Port 2 to GE6 - Circuit connection
Port 8 to Port 8 - Trunk port connection
GE1 to GE1 - SD-WAN (Velo cloud) connection


Appendix – TPX Equipment

Router – Physical Image	Speed	Ports	Power	Size	Version of Operating System
 <p>Adtran Switch</p>	24 Gbps (max. forwarding b/w)	8x 100/1000 Base-T port, 2x 1Gbps SFP Ports PoE+ Ethernet Switch	External AC 100 to 240V 50 – 60Hz Power load: 30 - 65W Plug Type: NEMA 5-15P	1.7 in. x 8.4 in. x 11.1 in. 4.3 cm x 21.3 cm x 28.3 cm (H x W x D)	N/A
<p><u>TPX Provided Equipment</u></p>  <p>Juniper Switch</p>	32Gbps	12x 10/100/1000BASE-T 2x 1Gbps SFP Ports	External AC: 100 -240V 50 – 60Hz Power load: 20W Plug Type: NEMA 5-15P	1.72 in x 9.4 in 10.98 x 4.4 x 23.9 cm x 27.9 (H x W x D)	Junos OS 21.4R3-S2.4

Wave 1	Wave 2	Wave 3
Counties & Implementation	Counties & Implementation	Counties & Implementation
Alameda – 1st week of June Alpine – 1st week of June Amador – 1st week of June	Monterey – 2 nd Week of July Napa - 2 nd Week of July Nevada - 2 nd Week of July	San Bernadino – 4th Week of Agust San Diego – 4th Week of August San Fransico – 4th Week of August
Butte - 1st week of June Calaveras - 1st week of June Colusa - 1st week of June	Orange - 2 nd Week of July Placer - 2 nd Week of July Plumas - 2 nd Week of July	San Joaquín – 4th Week of August San Luis Obispo – 4th Week of August San Mateo – 4th Week of August
Contra Costa - 1st week of June Del Norte - 1st week of June El Dorado - 1st week of June	Riverside – 2 nd and 5 th Week of July through 1 st Week of August Sacramento – 1 st Week of August San Benito – 1 st Week of August	Santa Barbara - 4th Week of August Santa Clara - 4th Week of August Santa Cruz – 4th Week of August Shasta – 5th Week of August
Fresno - 1st week of June Glenn - 1st week of June Humboldt - 1st week of June	San Bernadino – 2 nd Week through 4 th Week of August	Sierra - 5th Week of August Siskiyou - 5th Week of August Solano - 5th Week of August
Imperial – 2 nd week of June Inyo – 2 nd week of June Kern – 2 nd and 3 rd Week of June		Sonoma - 5th Week of August Stanislaus - 5th Week of August Sutter - 5th Week of August
Kings – 3 rd Week of June Lake – 3 rd Week of June Lassen – 3 rd Week of June		Tehama - 5th Week of August Trinity - 5th Week of August Tulare – 2 nd Week of September
Madera - 3 rd week of June Marin – 4 th Week of June Mariposa – 4 th Week of June		Tuolumne – 2 nd Week of September Ventura – 2 nd Week of September Yolo – 2 nd Week of September
Merced - 4 th Week of June Modoc - 4 th Week of June Mono - 4 th Week of June		Yuba – 2 nd Week of September LA County – TBD

Projected Timeline

Week 1	Week 2	Week 3	Week 4	Week 1	Week 2	Week 3	Week 4	Week 1	Week 2	Week 3	Week 4	Week 1	Week 2	Week 3	Week 4	Week 1	Week 2	Week 3	Week 4	Week 1	Week 2	Week 3	Week 4
May				June				July				August				September				October			



Key Project Technical Contacts

Role	Name	Email Address
CalSAWS Network (Project Manager)	Rosemary Assabil	assabilr@calaces.org
CalSAWS Network Engineers for CalWIN	Anitha Raju Arpita Kumari	rajua@calaces.org kumaria@calaces.org
County Scheduling and Communications (Email)	Offshore Network Team	Tech.Network.Onshore&Offshore@CalSAWS.org

Escalations

- Tech Network Rosemary Assabil assabilr@calaces.org
- Tech Network Uzair Naveed naveedu@calaces.org
- Consortium Pete Quijada quijadap@calaces.org

Note: For any escalation, please copy your County Regional Manager, TPOC and PPOC